Costing comparison Emesh Vs Steel mesh

		Cost$/unit	Units	Total cost
project size	100m2			
concrete thickness	100mm			
	Steel Mesh option			
Steel mesh	SL72	$66.00	8	$528.00
Chairs	50/65 pack of 100	$23.00	0.5	$11.50
Labour	man hrs	$50.00	2	$100.00
	Emesh option			
Emesh	4kg/m3	$12.00	40	$480.00

Emesh Material savings are $59.50 or $0.59/m2
labour saving is $100.00 or $1.00/m2

Total savings $159.50
$1.60/m2